

SECTION 04 72 00 – CASTSTONE MASONRY**PART 1: GENERAL****1.01 Scope of Standard**

- A. This standard provides general guidance concerning the specific preferences of the Texas State University caststone masonry
- B. Texas State University recognizes that project conditions and requirements vary, thus precluding the absolute adherence to the items identified herein in all cases. However, unless there is adequate written justification, it is expected that these guidelines will govern the design and specifications for Texas State University projects.

1.02 Reference Standards

- A. Refer to the Texas State University Campus Master Plan for guidelines pertaining to use of stone.
- B. Successful maintenance guidelines shall be developed and approved prior to the specification or installation of caststone.

1.03 Quality Control

- A. Details for installation and cleaning shall be approved by the Texas State University project representative prior to specification or installation of any caststone.

PART 2: PRODUCTS**2.01 Caststone**

- A. San Marcos Campus:
 - 1. Continental Caststone, #1101.T, “Greystone”, or equal color from other manufacturers. Other caststone manufacturers must match exactly Continental Caststone #1101-T. A custom color may be required.
No color substitutions.
- B. Anchors: Use only stainless steel.
- C. Mortar: Spectrum, Eldridge, “Khaki”.

SECTION 04 72 00 – CASTSTONE MASONRY

PART 3: EXECUTION

3.01 General

- A. Provide drips where caststone projects more than one inch.

- B. Provide caststone mock up for approval at least three months prior to needing caststone on site.

END OF SECTION 04 72 00